

EXHIBIT A
CONTRACTOR BID TABULATION SHEET

SPECIFICATION SECTION NO.	BID ITEM NO.	WORK TASK	UNIT	AMOUNT	COST PER BID UNIT	TOTAL BID ITEM COST
10	1	MOBILIZATION/DEMobilIZATION	LS	1		
11	2	PUMP REMOVAL AND INSPECTION	LS	1		
12	3	VIDEO SURVEY	EA	2		
13	4	CALIPER SURVEY	LS	1		
14	5	GRAVEL BACKFILL AND BENTONITE SEAL	LS	1		
15	6	CASING 8-INCH STAINLESS STEEL (0.25 WALL)	LF	198		
15	7	8X6-INCH REDUCER STAINLESS STEEL	LS	1		
15	8	CASING 6-INCH STAINLESS STEEL (0.25 WALL)	LF	152		
15	9	WELL SCREEN 6-INCH STAINLESS STEEL (0.06-INCH SLOT)	LF	130		
16	10	GRAVEL PACK	LF	290		
17	11	CEMENT SEAL	LF	195		
18	12	HIGH PRESSURE JETTING	LS	1		
19	13	DUAL SWAB AIRLIFT PUMPING	HR	6.5		
20	14	CHEMICAL INJECTION	LS	1		
20	15	CHEMICAL SWABBING (AGITATION)	HR	9.75		
20	16	AIRLIFT REMOVAL AND DISPOSAL	HR	6.5		

21	17	DISINFECTION	LS	1		
CONTRACTOR BID SHEET (CONTINUED)						
SPECIFICATION SECTION NO.	BID ITEM NO.	WORK TASK	UNIT	AMOUNT	COST PER BID UNIT	TOTAL BID ITEM COST
22	18	SUBMERSIBLE PUMP AND MOTOR	LS	1		
22	19	3-INCH GALVANIZED DROP PIPE	LF	315		
22	20	SUBMERSIBLE ELECTRIC CABLE	LF	320		
22	21	SUBMERSIBLE PUMP CHECK VALVES	EA	2		
22	22	STAINLESS STEEL AIRLINE AND GAGE	LF	320		
22	23	ELECTRICAL CONTROLS UPGRADE	LS	1		
22	24	DISSIMILAR METAL INSULATORS	EA	14		
22	25	DISCHARGE HEAD AND SURFACE PIPING	LS	1		
22	26	PUMP INSTALLATION	LS	1		
23	27	WELL FLUSHING	LS	1		
24	28	SITE CLEAN UP	LS	1		
					TOTAL	